# Randall Road at Big Timber Road Intersection Improvements

## VIRTUAL PUBLIC MEETING

February 25, 2021



# **Meeting Agenda**

#### **Welcome and Meeting Agenda**

#### 1. Project Introduction

Project Limits, Purpose and Need, What Was Analyzed, and Crash Data Q&A session

#### 2. Proposed Improvements

Geometry, Key Features, Typical Sections
Q&A Session

#### 3. Project Impacts

Environmental, Drainage, and Land Acquisition Q&A Session


### 4. Project Timeline

#### **Comments and Q&A Session**



# **Asking Questions**

#### Typing in the Chat Box



- Click on the Chat icon is located at the bottom of your screen.
- A Chat Box should appear on your screen.
- Type your question in the message box.
- Chat Box questions can be asked at any time.

#### **Verbally via Raise Hand**



- Click on the Reactions icon at the bottom or your screen.
- Click on Raise Hand command
- The host will be notified that you have raised your hand.
- Verbal questions will be taken during Q&A sessions.



# Rules of Engagement



This meeting will be recorded and available on the project website following the meeting.



# **Project Introduction**

Randall Road at Big Timber Road

# **Project Limits**



The signalized intersection of

Randall Road and Big Timber Road

is located in Elgin, IL and unincorporated

Kane County.

#### **Randall Road Limits**

Claude Hanson Bridge to Capital Street

#### **Big Timber Road Limits**

Gateway Drive to Jansen Farm Drive



### **Intersection Capacity**


- Existing intersection is at capacity with long queues and delays.
- Pavement widening is needed to accommodate future traffic growth along Randall Road.
- Turn lane storage lengths are not sufficient for existing or future traffic and need to be increased.





### **Intersection Geometry**

- Existing intersection skew is below standard.
- Existing truck turning geometrics need to be improved.





### Pedestrian Accommodations

- No existing pedestrian accommodations at or near the intersection.
- Provide connectivity between existing pedestrian facilities





### **Other Needs**

- Motorists currently use other routes to bypass intersection because of existing congestion.
- Emergency Vehicle access to and from Advocate Sherman Hospital is important.





# What was analyzed?



**Current Traffic Patterns and Volumes** 



**Crash Data** 



**Environmental Impacts** 



**Community Impacts** 



**Stakeholder and Property Owner Input** 



**Utilities** 



**Pedestrian and Bicycle Accommodations** 




**Drainage** 



## **Crash Data**

#### Randall Road at Big Timber Road, Years 2014-2018




### 336 TOTAL CRASHES, 2014-2018 89 TOTAL INJURIES


**INCLUDING 1 FATALITY** 

75% were Rear End or Turning which indicates congestion in the corridor.

#### **Injury Types**



#### **Crash Types**





# Questions?

**Project Introduction** 

Randall Road at Big Timber Road

#### **Key Features...**

#### Randall Road

- Three through lanes in each direction.
- · Dual northbound left turn lanes.
- Extend turn lane storage lengths.
- Southbound merge lane to accommodate the eastbound free flow right turn.

#### **Big Timber Road**


- · Realign existing roadway
- Free flow eastbound right turn
- Extend second westbound through lane
- Relocate driveway west of the intersection

These elements are expected to increase capacity and improve the safety of the intersection.






### Randall Road | North Leg






### Randall Road | South Leg





## Big Timber Road | West Leg





### Big Timber Road | East Leg







# Typical Sections | Randall Road

### **Existing**

Traveling
Northbound on
Randall Road









# Typical Sections | Randall Road

### **Existing**

Traveling
Southbound on
Randall Road









# Typical Sections | Big Timber Road

### **Existing**

Traveling **Eastbound** on
Big Timber Road









# Typical Sections | Big Timber Road

### **Existing**

Traveling
Westbound on
Big Timber Road







# Questions?

Proposed Improvements

# Project Impacts Randall Road at Big Timber Road

# **Environmental Impacts**

### **Wetland Impacts**

- Total of 14 sites were investigated
- 13 sites were classified as wetlands totaling 7.5 acres.
- **0.93 acres** of permanent Wetland Impacts.





# **Environmental Impacts**

#### **Trees**

- Approximately 33 trees impacted
- Trees will be replaced on a 1:1 basis according to IDOT Tree Replacement Policy where feasible
- Detailed landscaping plans completed during contract plan preparation





# **Noise Impacts**

#### Highway Noise is Dependent on...


- Traffic Volumes
- Traffic Composition
- Traffic Speeds
- Receptor Distance/Elevation

#### **Types of Noise Receptors**

- Single Family Homes
- Multi Family Homes
- · Hospital with Outdoor Space

The **distance** to Randall Road or Big Timber Road was the main component used to select receptor locations for this project.

Sound is produced by the vibration of air molecules as pressure waves and is measured on a logarithmic scale using units of decibels (dB).



Suburban Area

Background

Rustlina

Leaves

City Traffic

#### **Noise Analysis Results**

Noise levels are expected to increase from year 2020-2050.

Existing noise levels — 51-67 dB

No Build noise levels — 53-69 dB

Build noise levels — 52-69 dB

No Build noise levels increase due to traffic volume increases

**Build** noise levels increase due to the increase in traffic volumes and change in distance from source to receptor

Rock

Concert



# **Drainage**

### **Existing Drainage System**

- Storm Sewer System that drains through various outlets, ultimately discharging to Tyler Creek.
- Curb and gutter at all legs of the intersection with inlets and catch basins that drain into the storm sewer system.
- Existing detention basin along the north leg of Randall Road.
- Existing culverts on the west, east, and south legs of the intersection.





# **Drainage**

### **Proposed Drainage System**

- Maintain existing drainage patterns.
- Curb and gutter runoff collected into inlets and catch basins that drain into a new storm sewer system, ultimately draining to Tyler Creek.
- New reinforced concrete pipe culverts on the west, east, and south legs of the intersection.
- Stormwater mitigation/BMPs to reduce the volume of runoff and improve water quality.
- Additional detention storage provided to offset the impacts of new impervious areas.





# **Stormwater Mitigation and BMPs**

Measures taken to reduce the volume of runoff and improve water quality.

#### **Temporary BMPs** | Construction

- Temporary Seeding/Mulching
- Ditch Checks
- Perimeter Erosion Barriers
- Settlement Basins
- Perforated Riser

#### **Permanent BMPs**

- Riprap Erosion Protection
- Open Drainage System
- Permanent Seeding
- Catch Basins
- Detention Basin

BMPs = Best Management Practices





# **Land Acquisition**

#### TYPES OF LAND ACQUISITION

#### **Fee Simple Acquisition – 1.7 acres**

- Acquisition of all rights and interest
- Roadway widening and drainage improvements

#### Permanent Easements – 0.66 acres

- Partial ownership retained by property owner
- Allows permanent access to construct and maintain facilities

#### **Temporary Easements – 0 acres**

- Ownership retained by property owner
- Temporary use for a specified term or to completion of construction
- Driveway replacement and roadside grading

Total - 2.36 acres

#### LAND ACQUISITION PROCESS

Determine Ownership

Prepare Plat of Survey

Prepare Independent Appraisal Negotiations with Property Owners\*



<sup>\*</sup> Court Proceedings if Necessary

# **Questions?**

Project Impacts

# Project Timeline Randall Road at Big Timber Road

# **Project Timeline**

### PHASE I

Preliminary
Engineering &
Environmental Study

Summer 2021 Completion anticipated



We are here

### PHASE II

Contract Plan Preparation and Land Acquisition

Typically, 18-24 months

### PHASE III

Construction

Contingent upon plan readiness, land acquisition, and funding availability



## **Comments and Questions**

#### **Written Comments**

Multiple Ways to Submit

#### 1. Online at the Meeting

Type your comment/question in the Chat Box

#### 2. Google Form

Use the Google Form link during the public meeting or on the project website

#### 3. Comment Form

Visit project website to download comment form and mail to Project Manager.

#### 4. Email or Call Project Manager

### **Project Website**

http://kdot.countyofkane.org/Pages/Projects/Randall-BigTimber/Randall-BigTimber.aspx

# **Project Manager Contact Information**

#### Candi Thomas, P.E.

Kane County Division of Transportation 41W011 Burlington Road St. Charles, IL 60175

**Email**: thomascandance@co.kane.il.us

**Phone**: (630) 406-7355

Comments must be received by **March 19, 2021** to be included in public record.

